

See discussions, stats, and author profiles for this publication at: <https://www.researchgate.net/publication/221268176>

Safe and Reliable Metro Platform Screen Doors Control/Command Systems

Conference Paper · May 2008

DOI: 10.1007/978-3-540-68237-0_32 · Source: DBLP

CITATIONS

32

READS

3,162

1 author:



Thierry Lecomte

ClearSy System Engineering

54 PUBLICATIONS 418 CITATIONS

SEE PROFILE

Some of the authors of this publication are also working on these related projects:



AMASS - Architecture-driven, Multi-concern and Seamless Assurance and Certification of Cyber-Physical Systems [View project](#)



intoCPS [View project](#)

Safe and Reliable Metro Platform Screen Doors Control/Command Systems

Thierry Lecomte ¹

¹ ClearSy, Aix en Provence, France.

thierry.lecomte@clearsy.com

Abstract. *In this article we would like to present some recent applications of the B formal method to the development of safety critical system. These SIL3/SIL4' compliant systems have their functional specification based on a formal model. This model has been proved, guaranteeing a correct by construction behaviour of the system in absence of failure of its components. The constructive process used during system specification and design leads to a high quality system which has been qualified² by French authorities.*

1. Introduction

Historically, the B Method was introduced in the late 80s' to design correctly safe software. Promoted and supported by RATP³, B and Atelier B, the tool implementing it, have been successfully applied to the industry of transportation. First real success was Meteor line 14 driverless metro in Paris: Over 110 000 lines of B models were written, generating 86 000 lines of Ada. No bugs were detected after the proofs, neither at the functional validation, at the integration validation, at on-site test, nor since the metro lines operate (October 1998). The safety-critical software is still in version 1.0 in year 2007, without any bug detected so far. Today, Alstom Transportation Systems and Siemens Transportation Systems (representing 80% of the worldwide metro market) are the two main actors in the development of B safety-critical software development. Both have a product based strategy and reuse as much as possible existing B models to develop future metros. For the time being, ClearSy has developed for Siemens the biggest B application: the Charles de Gaulle airport shuttle automated pilot is a 150 000 lines of code program. On a different domain, Gemplus has developed a smartcard java bytecode verifier [Casset 99].

A more widely scope use of B appeared in the mid '90s, called *Event-B*, to analyze, study and specify systems. One of the outcome of *Event-B* is the proved definition of systems architectures and, more generally, the proved development of, so called, "system studies", which are performed before the specification and design of the software. This enlargement allows one to perform failure studies right from the beginning in a large system development. *Event-B* has been applied in many cases to various fields:

¹SIL (Safety Integrity Level) is defined as a relative level of risk-reduction provided by a safety function, or to specify a target level of risk reduction. Four SIL levels are defined, with SIL4 being the most dependable and SIL1 being the least. A SIL is determined based on a number of quantitative factors in combination with qualitative factors such as development process and safety life cycle management.

² French authorities define Qualified as « Certified and working » while Certified is mainly a verification of conformance to specification (the system produced may or may not work properly).

³ Régie Autonome des Transports Parisiens : operates bus and metro public transport in Paris

certification of smartcard security policies (level EAL5+, Common Criteria), verification of Ariane 5 launcher embedded flight software, generation of proven hardware specification, etc.

In this article, we detail the first platform screen door system which has been modelled in B, details the development process and presents qualitative and quantitative results.

2. COPPILOT: A platform screen door controller

2.1. Presentation

In France, RATP has used for years platform screen doors (PSD) that prevent customers to enter or to fall on tracks. Such a system was adopted by the METEOR driverless metro, as it dramatically improves trains availability. In order to offer higher quality services and more safety to its customers, RATP was trying to introduce this kind of protection system in several lines, automated or not. For practical reasons, trains and cars could not be modified with the introduction of PSD. Before starting to deploy a new PSD system in an entire line, RATP initiated a project aimed at developing a prototype PSD system for three stations of line 13.

These prototypes would be evaluated during eight months. ClearSy was in charge of developing the SIL3 compliant (probability of system failure less than 10^{-7}), control command controller. This controller is in charge of detecting the arrival, presence at a standstill and departure of trains without direct connection with them (on the contrary, Meteor⁴ trains communicate with PSD through dedicated communications lines). Once the train is at standstill, the controller should be able to detect train doors opening and closing, and then issue PSD opening and closing orders. These orders have to be securely issued (failure by elaborating a wrong opening order may lead to customers injury or death), and controller have to be designed, tested and validated in accordance with railway regulations (IEC 50126, 50128, 50129 in particular).

The timescale of this project was quite short as the PSD controller would be installed in only 10 months after the beginning of the project. Given these strong timing constraints, we decided to adopt a secure architecture able to be quickly qualified by regulation authorities, loosely coupled with sensor technology. The final architecture was based on Siemens safety automaton, SIL3 compliant, and ordinary infra-red and radar sensors. In this case, security relies on the safety automaton and on sensor measure redundancy, not on the safety properties of the sensors. This approach leads to a decrease in system costs as usual since non-safety sensors are really cheaper than safety ones, leading to easier provisioning (shorter delay, no dependency towards a unique provider).

2.2. The development process

In order to reach the required safety level during project timescale, we decided to set up a development method aimed at reaching targeted reliability, and also ensuring traceability between the different stages of the projects in order to reduce the validation effort. This method was heavily based on the B formal method, and applied during most phases of the project.

⁴ First driverless metro operated in Paris

Before any development activity, a formal functional analysis of the system was performed, to evaluate “completeness” and ambiguity freeness of the statement of work. At that time, the solution imagined by RATP was to point two laser telemeters on the platform, and to apply two independent 2D image recognitions in order to detect train arrival and departure, as well as train door opening and closing. The B method was used to:

- Verify on the overall system (PSD + controller) that functional constraints and safety properties were verified (no possibility to establish forbidden connections between train and platform or between train and tracks).
- Lead to the observation of dangerous system behaviour.

Telemeter based solution was then evaluated in order to verify that its compliancy with project constraints. This solution was finally abandoned due to the fact that designing two independent (but concordant) image recognition algorithms was judged too risky during the short lifetime of the project.

A new architecture was then imagined and proposed, making use of usual sensors and processing based on temporal sequence recognition of sensor events. Hyper frequency, infrared and laser sensors help to improve system resistance to various perturbations. Redundancy among sensors using different technology raises measures confidence. These sensors were positioned on the platform and pointed to the tracks in order to measure train position, train speed and train door movements.

System and software specification were then formalized in B by the development team, taking into account only nominal behaviour for the sensors (in absence of perturbation). Models obtained from previous functional analysis (independent from any PSD controller architecture) were directly reused. The proposed architecture was modelled and inserted in these previous models. New architecture was successfully checked by proof to comply with functional specification of the system, including parts of the French underground regulations. Controller functions were then precisely modelled (train arrival, train detection, train departure, train door opening, train door closing, etc). In the meantime, an independent safety case⁵ was developed in parallel by the security team, in order to precisely define how external perturbations may influence the behaviour of the PSD controller. Perturbations were given a priori or a posteriori frequencies, depending on availability of such data at RATP, and a mathematical model, independent from the B model, was set up in order to determine quantitatively the security level of the system. A priori frequencies were verified during the eight month experiment. In case these frequencies were not verified and lower system security below SIL3 level, the PSD controllers would have to be redesigned considering this new information.

The resulting B model was animated with the Brama animator⁶, in order to verify on given scenarios that the model produced was corresponding to the real system we were modelling. This model animator was not part of the validation process, as this would require it to be qualified as a SIL3 software, but it helped us to check models against reality and to internally verify their suitability.

Specification documentation was partly elaborated from the system level models developed during this project. The composys⁷ tool helps the modeller to add contextual

⁵ Safety oriented study that provides a convincing and valid argument that a system is adequately safe for a given application in a given environment.

⁶ <http://www.brama.fr>

⁷ <http://www.composys.fr>

information (comments, description, component name, etc) in B models that are used to generate in natural language the specification documentation describing the complete system. As events are associated to components and as variables are used within events (read/write), Composys computes relationships among components constituting the system being modelled, depending on how variables are read or modified. This document was used to check models with experts of the domain, unable to read and understand formal models.

The development of the software was based on the formal models, as B enables the production of source code, proven to comply with its specification. Siemens automaton can be programmed in the LADDER language but, unfortunately, requires entering program source code via its graphical interface (according to its certificate) to keep its SIL3 accreditation. A dedicated translation schema (from B to LADDER) was elaborated. B to LADDER state diagrams translation is straightforward and some optimisations were introduced in order to verify temporal constraints (cycle time in particular). During validation phase, one can determine which event of the B model corresponds to the path of the LADDER program for a cycle (a LADDER program is defined by logical equations and is analyzed in term of execution path). In case the source code is automatically generated by a qualified translator (as for automatic pilots, by Siemens and Alstom), no unit test is required, this testing phase being covered by the proof of the model. In this project, as the source code was not generated automatically by such a translator, test was required and test specification was elaborated by usual means. Some months after the beginning of the project, we obtained a fully functional, tested and validated application. The process described above has enabled us to produce a 100% tested, error free (against its specification) software when running validation test bench for the first time. A dedicated test bench was designed to simulate major perturbations (sensors were emulated) and run during days, but no faulty behaviour was observed.

Integration testing was performed on a dedicated testing platform installed in the METEOR line. Tracks and sensors being already protected by PSD in the line, measurement campaigns were setup quickly in order to assess as quickly as possible security, availability, response time, etc). Sensor technology choices were validated at that occasion.

2.3. Results

Finally, 4 months after the beginning of the project, the PSD controller was deployed on 3 platforms on line 13, for a 8 month experiment. The following metrics were obtained:

- equip: a project manager, a developer, a validation engineer, a safety engineer
- initial system level functional specification: 130 page document
- safety case: 300 pages
- development documentation: 600 pages
- formal B models: 3500 lines of code, representing about 1000 proof obligations. 90 % were demonstrated automatically, the remaining proof obligations were discharged in two days with the Atelier B interactive prover.

This system was experimented during 8 months, controlling around 96 000 trains. No fault was observed. Hypotheses made during the safety case were confirmed and made more accurate. System availability conformed to expectations and, after initial setup and tuning, no passenger remained stuck in the train (PSD should open 9999 out of 10000 times when a valid train is at standstill opening its doors).

3. Conclusion

The methodology we have developed appears to be efficient and well suited to address projects requiring high level of safety and short development time. The B formal method was not initially considered by RATP, but is now well accepted. The writing of some extra documents were required to help RATP engineers to fully understand, verify and qualify our deliverables. Reuse of existing models for similar projects proved to be efficient.

The resulting systems are nowadays deployed worldwide.

References

Burdy, L.(1996) , *Automatic Refinement. In Proceedings of BUGM at FM'99*

Sabatier, D. & al (2006), *Use of the Formal B Method for a SIL3 System Landing Door Commands for line 13 of the Paris subway*, Lambda Mu 15